CONIFEROUS TREE

22B SOIL TYPE ----

EDGE OF GRAVEL DRIVE — · — · —

🖶 🖶 SPIKE FND/SET

MAGNAIL (PK) FND/SET

▲ △ HUB & TACK FND/SET

· — 

GUY ANCHOR

BUILDING SETBACK LINE


DRAWN BY ; CTB

SCALE ; 1" = 200'

PO BOX 189

DATE OF PLAN: January 2023

GILMANTON, NH 03237



▲ △ HUB & TACK FND/SET

EDGE OF GRAVEL DRIVE — · — · — · —


SOILS INFORMATION


SHEET 3 OF

WETLAND DELINEATION CERTIFICATION

DATE OF PLAN: January 2023

SHEET 4 OF 6





1. ALL ROADWAY CONSTRUCTION MATERIALS AND METHODS SHALL BE IN ACCORDANCE WITH NHDOT (NEW HAMPSHIRE DEPARTMENT OF TRANSPORTATION) SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION,

2. WEARING COURSE SHALL MEET A MODIFIED NHDOT 304.2; 100% PASSING THE 1 1/4" SIEVE, 25-70% PASSING THE #4 SIEVE, 0-12% PASSING THE #200 SIEVE.

3. THE SUB BASE (BANK RUN GRAVEL) COURSE SHALL MEET THE NHDOT ROAD AND BRIDGE SPECIFICATION SEC. 304.2

4. THE UPPER BASE (CRUSHED GRAVEL) COURSE SHALL MEET THE NHDOT ROAD AND BRIDGE SPECIFICATION SEC. 304.3

5. UNDERDRAINS SHALL BE INSTALLED WHERE FIELD CONDITIONS FIND THAT SEASONAL HIGH WATER TABLE IS WITHIN FOUR FT. (4') OF THE ROAD SUB BASE LAYER, OR AS DIRECTED BY THE MUNICIPAL ROAD

AGENT OR BY THE PROJECT ENGINEER. UNDERDRAIN PIPE SHALL DISCHARGE THROUGH A MORTARED RUBBLE MASONRY ENDWALL (OR EQUIVALENT,) OR INTO A CATCH BASIN. 6. CULVERTS SHALL BE SMOOTH BORE HDPE PIPE, SEALED IN ACCORDANCE WITH SPECIFICATIONS AS SET FORTH BY THE MANUFACTURER.


WWW.FILTREXX.COM).

ÈILTREXX CERTIFIED™ SEAL.

7. ANY DEVIATION FROM THE APPROVED PLANS AND SPECIFICATIONS MUST BE APPROVED IN WRITING BY THE APPROPRIATE OFFICIAL OF THE MUNICIPALITY AND THE PROJECT ENGINEER.

## EROSION CONTROL NOTES for MINOR PROJECTS

- DURING CONSTRUCTION AND THEREAFTER, EROSION CONTROL MEASURES ARE TO BE IMPLEMENTED AS NOTED. THE SMALLEST PRACTICAL AREA OF LAND SHOULD BE EXPOSED AT ANY ONE TIME DURING THE DEVELOPMENT. WHEN LAND IS EXPOSED DURING DEVELOPMENT, THE EXPOSURE SHOULD BE KEPT TO THE SHORTEST PRACTICAL PERIOD OF TIME.
- WHERE NECESSARY, TEMPORARY VEGETATION OR MULCHING AND STRUCTURAL MEASURES MAY BE REQUIRED TO PROTECT AGAINST EROSION OF THE EXPOSED AREA DURING CONSTRUCTION.
- 3. SILT SOXX SEDIMENTATION TRAPS SHALL BE INSTALLED AND MAINTAINED DURING AND AFTER CONSTRUCTION, AS REQUIRED, TO REMOVE SEDIMENT FROM SITE RUN-OFF AND FROM THE ONGOING DEVELOPMENT AREA. WHERE POSSIBLE, NATURAL DRAINAGE-WAYS SHALL BE UTILIZED AND LEFT OPEN TO REMOVE EXCESS SURFACE WATER. HAY BALE BARRIERS ARE TO BE MAINTAINED AND CLEANED UNTIL ALL SLOPES HAVE A HEALTHY STAND OF GRASS.
- . ALL CUT SLOPES SHALL BE LOAMED, SEEDED AND MULCHED IMMEDIATELY AFTER GRADING TO PROVIDE CONTROL OF SURFACE RUNOFF.
- ALL DISTURBED AREAS SHALL BE LOAMED AND SEEDED. A MINIMUM OF 4" OF LOAM SHALL BE INSTALLED WITH NOT LESS THAN 20 LBS/AC. OF CREEPING RED FESCUE, AND 8 LBS/AC. OF BIRDSFOOT TREFOIL. [TOTAL OF 48 LBS/AC.] HAY MULCH SHALL BE APPLIED AND HELD IN PLACE WITH JUTE MATTING PINNED DOWN AT 15' INTERVALS WHEN REQUIRED. THESE SPECIFICATIONS ARE FOR "NORMAL" SOIL WITH A pH OF AROUND 7. ACCORDING TO SOIL TESTS, THE SEEDING AND FERTILIZING MUST BE ADJUSTED FOR VERY ACIDIC OR ALKALINE
- 5. THE FILL MATERIAL SHALL BE FREE FROM STUMPS, WOOD, ROOTS, ETC. AND SHALL BE FREE
- 7. IF ANY CHANNELS ARE REQUIRED AS PER THE GRADING PLAN, THE CONSTRUCTION OF CHANNELS SHALL BE COMPLETED IN THE INITIAL PHASE OF THE PROJECT.
- WHEN CALLED OUT ON THE EROSION CONTROL PLAN, SILT SOXX BARRIERS SHALL BE INSTALLED DURING CONSTRUCTION OF CHANNEL AND DITCH LINES, IN LOCATIONS SHOWN ON THE CONSTRUCTION PLANS AND ALL OTHER AREAS WHEN REQUIRED BY SITE CONDITIONS. REFER TO DETAILS ON THIS PLAN FOR THE PROPER INSTALLATION OF SILT SOXX BARRIERS
- ). ALL EROSION CONTROL PROCEDURES SHALL CONFORM TO PRACTICES SHOWN IN THE  ${
  m \underline{NEW}}$ HAMPSHIRE STORM WATER MANUAL, VOLUMES 2 & 3, AS PUBLISHED BY THE NEW HAMPSHIRE DEPARTMENT OF ENVIRONMENTAL SERVICES, DATED DECEMBER 2008 OR LATER.
- LO. SEDIMENT BASINS, WHEN REQUIRED, SHALL BE PROPERLY MAINTAINED. THE BOTTOMS OF THE BASINS SHALL PERIODICALLY BE CLEANED AND THE SEDIMENT REMOVED TO A SECURE LOCATION TO PREVENT SILTATION OF NATURAL AND MANMADE WATERWAYS. THE MAXIMUM AMOUNT OF DISTURBED AND UNSTABILIZED AREA TO BE EXPOSED AT ANY ONE TIME SHALL NOT EXCEED 50,000 S.F. THE MAXIMUM TIME AN AREA CAN BE DISTURBED AND UNSTABILIZED IS 30 DAYS. ALL EARTH STOCKPILES SHALL BE STABILIZED AND PROTECTED TO PREVENT
- 11. ALL TEMPORARY EROSION CONTROL SYSTEMS SHALL BE INSPECTED WEEKLY AND WITHIN 24 HOURS AFTER EVERY 0.5 INCH RAINFALL EVENT.



SILTSOXX SILTATION BARRIER **DETAILS** 

WORK AREA — SILTSOXX GRADE STAKE  $\sim\sim\sim\sim$ AREA TO BE PROTECTED FROM حر SEDIMENTATION

PLAN VIEW SCALE: 1"=10'

DISTURBANCE. PRODUCING ADEQUATE HYDRAULIC FLOW-THROUGH. IF PONDING BECOMES EXCESSIVE, ADDITIONAL SILTSOXX™ MAY BE REQUIRED TO REDUCE EFFECTIVE

SLOPE LENGTH OR SEDIMENT REMOVAL MAY BE NECESSARY. SILTSOXXTM SHALL BE 4.SILTSOXX TM SHALL BE MAINTAINED UNTIL DISTURBED AREA ABOVE THE DEVICE INSPECTED UNTIL AREA ABOVE HAS BEEN PERMANENTLY STABILIZED AND HAS BEEN PERMANENTLY STABILIZED AND CONSTRUCTION ACTIVITY HAS CEASED

5. THE FILTERMEDIA™ WILL BE DISPERSED ON SITE ONCE DISTURBED AREA HAS BEEN PERMANENTLY STABILIZED, CONSTRUCTION ACTIVITY HAS CEASED, OR AS DETERMINED BY THE ENGINEER. IN WINTER LAKE CONDITIONS, DO NOT ALLOW ANY I. THE CONTRACTOR SHALL MAINTAIN THE SILTSOXX™ IN A FUNCTIONAL CONDITION AT ALL TIMES AND IT SHALL BE ROUTINELY INSPECTED. FREE MEDIA TO REMAIN ON THE LAKE ICE.

6. FOR LONG-TERM SEDIMENT AND POLLUTION CONTROL APPLICATIONS, SILTSOXX™ CAN BE SEEDED AT THE TIME OF INSTALLATION TO CREATE A VEGETATIVE FILTERING SYSTEM FOR PROLONGED AND INCREASED FILTRATION OF SEDIMENT AND SOLUBLE POLLUTANTS (CONTAINED VEGETATIVE FILTER STRIP). THE APPROPRIATE SEED MIX SHALL BE DETERMINED BY THE ENGINEER. 3. THE CONTRACTOR SHALL REMOVE SEDIMENT AT THE BASE OF THE UPSLOPE SIDE OF THE SILTSOXX<sup>TM</sup> WHEN ACCUMULATION HAS REACHED 1/2 OF THE EFFECTIVE HEIGHT OF THE SILTSOXX<sup>TM</sup>, OR AS DIRECTED BY THE ENGINEER. ALTERNATIVELY, A NEW SILTSOXX<sup>TM</sup> CAN BE PLACED ON TOP OF AND SLIGHTLY BEHIND THE ORIGINAL ONE CREATING MORE SEDIMENT STORAGE CAPACITY WITHOUT SOIL

7. COMPOST MEDIA SHALL BE DISPOSED OF ONSITE UNLESS SPECIFIED BY THE

TAX MAP 414 LOT 93

## BAILEY ASSOCIATES

CONSTRUCTION ACTIVITY HAS CEASED.

LAND SURVEYING & LAND PLANNING ENGINEERING & NATURAL RESOURCE SCIENCES WWW.BAILEY-ASSOCIATES.COM (603) 528-3734

INSPECTED UNTIL AREA ABOVE HAS BEEN PERMANENTLY STABILIZED AND

2. IF THE SILTSOXX™ HAS BEEN DAMAGED, IT SHALL BE REPAIRED, OR REPLACED IF BEYOND REPAIR.


LAND OF DARYL BREED HOITT LIVING TRUST LAND LOCATED AT JOE JONES ROAD AND ROUTE 140, GILMANTON NH

DEED: BK. 2954 PG. 930

159 JOE JONES ROAD PO BOX 189

GILMANTON, NH 03237

DATE OF PLAN: January 2023



SILTSOXX SILTATION INSTALLATION

AND STORM WATER RUNOFF FILTRATION DEVICE TYPICALLY USED FOR

POLLUTANTS IN STORM RUNOFF SHALL MEET

FILTREXX SILTSOXX™ ARE A THREE-DIMENSIONAL TUBULAR SEDIMENT CONTROL

PERIMETER CONTROL OF SEDIMENT AND OTHER SOLUBLE POLLUTANTS (SUCH AS

.SILTSOXX™ USED FOR PERIMETER CONTROL OF SEDIMENT AND SOLUBLE


FILTREXX SOXX™ MATERIAL SPECIFICATIONS AND USE CERTIFIED FILTREXX

PHOSPHORUS AND PETROLEUM HYDROCARBONS), ON AND AROUND CONSTRUCTION

PURPOSE & DESCRIPTION

INSTALLATION

FILTERMEDIATM.



12 IN (300MM), AND 8 IN (200MM) FOR CLAY SOILS. 6.LOOSE COMPOST MAY BE BACKFILLED ALONG THE UPSLOPE SIDE OF THE SILTSOXX™, FILLING THE SEAM BETWEEN THE SOIL SURFACE AND THE DEVICE, IMPROVING FILTRATION AND SEDIMENT RETENTION.

STAKES. IN THE EVENT STAKING IS NOT POSSIBLE, I.E., WHEN SILTSOXXTM ARE

USED ON PAVEMENT, HEAVY CONCRETE BLOCKS SHALL BE USED BEHIND THE SILTSOXX™ TO HELP STABILIZE DURING RAINFALL/RUNOFF EVENTS. ICE

INSTALLATIONS REQUIRE THE SILTSOXX TO BE FROZEN TO THE BARE LAKE ICE.

ROUTINE INSPECTION SHOULD BE CONDUCTED WITHIN 24 HRS OF A RUNOFF EVENT

OR AS DESIGNATED BY THE REGULATING AUTHORITY. SILTSOXX™ SHOULD BE

REGULARLY INSPECTED TO MAKE SURE THEY MAINTAIN THEIR SHAPE AND ARE

5. STAKING DEPTH FOR SAND AND SILT LOAM SOILS SHALL BE

2.SILTSOXX $^{\text{TM}}$  WILL BE PLACED AT LOCATIONS INDICATED ON PLANS AS DIRECTED BY THE ENGINEER 3. SILTSOXX™ SHOULD BE INSTALLED PARALLEL TO THE BASE OF THE SLOPE OR OTHER DISTURBED AREA. IN EXTREME CONDITIONS (I.E., 2: I SLOPES), A SECOND INSPECTION AND MAINTENANCE SILTSOXX™ SHALL BE CONSTRUCTED AT THE TOP OF THE SLOPE.

1. CONTRACTOR IS REQUIRED TO BE FILTREXX CERTIFIED™ AS DETERMINED BY

IDENTIFICATION IS SHOWN DURING TIME OF BID OR AT TIME OF APPLICATION

(CURRENT LISTING CAN BE FOUND AT WWW.FILTREXX.COM). LOOK FOR THE

FILTREXX INTERNATIONAL, LLC (440-926-2607 OR VISIT WEBSITE AT

CERTIFICATION SHALL BE CONSIDERED CURRENT IF APPROPRIATE

4. STAKES SHALL BE INSTALLED THROUGH THE MIDDLE OF THE SILTSOXX ™ ON 10 FT (3M) CENTERS, USING 2 IN (50MM) BY 2 IN (50MM) BY 3 FT (I M) WOODEN

**DETAILS** 

PROPERTY OWNER: DARYL BREED HOITT LIVING TRUST DARYL BREED HOITT, TRUSTEE

SHEET 6 OF